App F IX 1

Previous References

1946 47
(mul)

File No 13/46
Serial Nos. 87

Later References
on 75-47 19

GENERAL AND REVENUE SECRETARIAT

Serial Nos One

Part B for April 47

SUBJECT

Estimate for Rs 850 - to Connect the present terminal of the old Sewer to the Storm Water main at the Head Point.

L 13446-47 dt 5-4-47

To -- Chairman C I T B
Comptroller & Sols
-- Chief Engr R I T B
Mr Connell B. Sc
Ch

I am chosen the

7480/2

From the chairman, Trust board
Bangalore

No 2376 dt 10/3/47

Encl 6 25/7/0

Requests sanction to an estimate for Rs 850/- to connect the present terminal of the ~~drain~~ domed sewer which is located at the head of the Koramangala Canal to the storm water drain at the nearest point

submitted with a draft- to sanctioning the above estimate

As seen from the report accompanying the estimate, the cost in this behalf will be met out of the funds of the comprehensive drainage scheme of Bangalore

14/3/47

May be approved
14/3/47

May be approved
Minister for Rev Dept
23/3

26/3/47

Sanction the proposal

2/13444-7 5/4/47

7/4/47

TYPING SECTION
27 MAR 1947
SECTT

SECRETARIAT
FOR EDUCATION DEPT
Date 25/3
No 6 Edn 5

C F No 46]

GOVERNMENT OF MYSORE.

No 2376
Encls

OFFICE OF the Chairman,
City Improvement Trust Board, Bangalore,

Date 10th March 1947

To

The Secretary to Government,
Revenue Department, BANGALORE.

Sir

I have the honour to state that the Engineer - Officer of the Trust Board reported on 1-2-1947 that it was necessary to connect the present terminal of the Ovoid Sewer which is located at the head of Kormangala tank and which is at a level of 3-1/2 feet - below the ground level to the storm water main at - the nearest point to get the newly constructed ovoid sewer to function and prepared an estimate for the work costing Rs 850/- This was considered by the Board at its meeting held on 20-2-47 and the Board resolved "that the estimate for Rs 850/- be approved and sent to Government for sanction I accordingly request that sanction of Government may kindly be obtained to the enclosed estimate for Rs 850/- for the work The report accompanying the estimate furnishes the necessity for and the details of the work A rough

P.T.O.

rough sketch plan is also enclosed for reference.

I have the honour to be
Sir,
Your most obedient servant,
G V Naroyan
CHAIRMAN.

REPORT TO ACCOMPANY THE ESTIMATE FOR EXCAVATING A CHANNEL FOR LINKING OVOID SEWER FROM M H 82 to FLOOD WATER MAIN DRAIN BETWEEN

The present terminal of Ovoid sewer is located at the head of Koramangala Tank and is at a level 3½' below Ground level It is necessary to connect this to the Storm water main drain at the nearest point to get the newly constructed Ovoid sewer to function, hence the estimate.

The estimate provides for excavating a contour channel in a gradient of 1 in 700 with a velocity of 3' and discharging capacity of 17 Cusecs

Provision has been made for constructing rough stone revetment of 1½' with jelly packing to protect the sides from scouring

rate

The current/has been proposed for the several items

The amount of the estimate comes to Rs 850/- and will have to be met out from the funds of the comprehensive Drainage Scheme of Bangalore City

Y Ramastamy

ENGINEER OFFICER, 2-2-47

G R S App F VI—G 2]

SUBJECT

4 Copies

A.D.

Diary No of let'er replied to

General and Revenue Secretariat

( ) }
the *194* }

Date of issue 5/4/ 194 }

Signed by M G R Rao

Section Mal

File No 13-46

Serial No 97

Proceedings of the Government of His Highness the Maharaja of Mysore

May this be—

(i) printed ?

(ii) treated as a Standing Order ?

(iii) published in the Gazette English Part ?

(iv) translated ?

(v) placed at the disposal of the Press ?

(iv) published in the Gazette Kannada Part ?

Read— Letter No 2376 dt 10-3-47 from the chairman, City Improvement Trust Board, Bangalore requesting sanction to an estimate for Rs 850/- for connecting the present terminal of the Dvora sewer which is located at the head of the Koramangala tank to the storm water drain at the nearest point - the water course

Order thereon—No

P T O

No. 13446-
Order No 2 dt. 5-4-46
Sanctioned. The cost
in this behalf will be
met out of the funds of the
~~Bangalore~~ Comprehensive Drainage
Scheme of Bangalore.

H.L. 23/3
for Rev Secy

To,

The Chairman C I Trust, Bangalore with reference
The Controller
The Chief Engineer for R&B
71 Civil Works (Thro the Secretary)

List of Enclosures

Copied by

Examined by

WD 04162—GPB—60 000—23-10-41